ENGINEERING DEPARTMENT.

KOLAR DIVISION.

Dated 12th June 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M., of 5th July 1929, for Restoring Kiruvani Major Tank, Mulbagal Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M., to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 400 only in cash or Government Promissory Notes, as earnest money, and be superscribed " Tender for Restoring Kiruvani Major Tank, Mulbagal Taluk " in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The tenderers must quote specific rates for each item of work both in words and in figures.

10. The tenderers stating that the work would be executed at a certain percentage in excess or lower than the estimate will not be accepted.

Detailed abstract estimate of Kiruvani Tank, Reg. No. 488 of Mulbagal Taluk.

No.	Items of work	Per	Quantity	Rate	Cost	Total
	Bund at R. L. 55·00			Rs. a. p.	Rs.	
1	Earthwork to bund including watering and tamping lead and lift, etc.	C.yds.	10,325			
2	Turfing to bund	S.yd.	7,210			
3	Revetment new stone with new jelly ...	C.yds.	1,290			
4	Revetting old stone revetment ...	,,	1,000			
5	Grade stones including zero stone ...	No.	29			
6	Index stones	,,	29			
7	Register No. stone with construction details.	,,	1			
8	Gauge stones	,,	1			
9	B. M. stones	,,	2			
10	Jungle clearing with roots and removing hills and bund, etc., complete.	Per grade	...			
	Total to bund ...	...	...	...	...	...
	Sluice No. I at R. L. 45·00.					
1	Earthwork excavation	C.yds.	83			
2	Surki mortar concrete	C.ft.	118			
3	Brick in surki mortar	,,	587			
4	Plastering with mortar	Sqr.	6·00			
5	Burnt stone slabs 6" thick... ...	S.ft.	284			
6	Iron rod with wooden plug and locking arrangements, etc.	Lump sum	Rupees			
7	Boring holes, etc., in stone slab ..	Lump sum	Rupees			

No.	Items of work	Per	Quantity	Rate	Cost	Total
	Sluice No. II at R. L. 45·00.			Rs. a. p.	Rs.	
1	Surki mortar concrete	C.ft.	118			
2	Brick in surki mortar	,,	587			
3	Plastering with surki mortar ...	Sqr.	6·00			
4	Burnt stone slabs 6″ thick ...	S.ft.	248			
5	Iron rod with wooden plug and locking arrangements.	Lump sum	Rupees			
6	Boring holes in stone slabs ...	Lump sum	Rupees			
7	Earthwork as per No. 1 sluice ...	C.yd.	83			
	Total to sluice ..	...	...	..	...	...
	Waste weir 90′ long and 60′ existing one at R. L. 50·00					
1	Earthwork excavating foundation ...	C.yd.	83			
2	Concrete burnt brick in surki mortar ...	C.ft.	293			
3	Burnt brick in surki mortar ...	,,	942			
4	Plastering with surki mortar ...	Sqr.	10·20			
5	Burnt stone slabs 6″ thick... ..	S.ft.	463			
6	Rough stone work	C.yds.	135			

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

MYSORE DIVISION.

Notice No. 1680—2, *dated 7th June* 1929,

RESTORING KULUGERE DODDAKERE MAJOR TANK, MALVALLI TALUK.

"Reference is invited to the advertisement published in detail in the *Mysore Gazette*, dated 13th June 1929 intimating the last date of tender for restoring Kulugere Doddakere Major Tank, Malvalli Taluk."

N. KRISHNIENGAR,
Executive Engineer.

SHIMOGA ARASALU RAILWAY, CONSTRCTION DIVISION.

Abstract Notification dated 14th June 1929.

The attention of the public is invited to the Notification dated 8th June 1929, calling for tenders for construction of buildings on Shimoga-Arasalu Railway, published in extenso in page 590 part VI of *Mysore Gazette*, dated 13th June 1929. The last date for receiving tenders is 3rd July 1929 up to 12 noon.

Tender forms can be had from the undersigned on payment of Re. 1 per form.

Y. K. RAMACHANDRA RAO,
Executive Engineer.

KADUR DIVISION.

Abstract Notification dated 5th June 1929.

"The attention of the Depositors and their heirs is drawn to the notice published on pages 573 & 574, dated 23rd May 1929, Part VI of the *Mysore Gazette*. The amounts if not claimed before the 30th of this month will lapse to Government".

Abstract Notification dated 31st May 1929.

The attention of the public is invited to the notice calling for tenders for constructing "A New Dispensary at Javali" Mudgere Taluk. Last date 25th June 1929 till 3 P.M.

Abstract Notification dated 31st May 1929.

"The attention of the public is invited to the notice calling for tenders for raising the waste weir of the Indavara Huligunda tank, Chikmagalur Taluk, published on pages 542 and 543 of in Part VI of the *Mysore Gazette*, dated 6th June 1929. The last date for receiving tender is 25th June 1929, till 3 P.M."

Abstract Notification dated 6th June 1929.

"The attention of the public is invited to the notice calling for tenders for constructing "*A New Dispensary*" at Javali Mudigere Taluk, latest date for receiving tenders 1st July 1929, deposit Rs. 600".

B. KRISHNA RAO,